


CONSTRUCTION NOTES

- #1 TO #4 NOT-IN-USE
- 5 TILE FLOOR
- 6 HARDWOOD FLOOR
- 7 TYP "X" GYP. BD. WALLS & CEILINGS
- 8 WOOD TREADS & RISERS
- 9 WROUGHT IRON GURADAIL (42" MIN)
PROVIDE 42" HIGH GURAD WITH MAX 4" CLEAR
SPACING OPENING BETWEEN RAILS
- 10 ATTIC ACCESS - MIN 20" X 30"
- 11 TEMP. GLZ SHOWER DOOR & ENCLOSURE
- 12 SCUPPER & OVERFLOW
- 13 MER-KO WEATHER DECK - LA.RR. 23811
- EXHAUST FAN - SEE SHEET GRN-1
- SD SMOKE DETECTOR

NOTES: - ENCLOSED USEABLE SPACE UNDER INTERIOR
STAIR REQUIRES ONE HOUR FIRE RESISTIVE
CONSTRUCTION ON ENCLOSED SIDE
- PROVIDE 90" HIGH NON-ABSORBENT WALL
ADJACENT TO SHOWER AND APPROVED is approved for
WATER RESISTANT MATERIALS FOR SHOWER ENCLOSURES.
This set of plans MUST be at the job site during construction
- ALL INTERIOR AND EXTERIOR STAIRWAYS SHALL BE ILLUMINATED
- BATHROOMS, WATER CLOSET COMPARTMENTS AND OTHER
SIMILAR ROOMS SHALL BE PROVIDED NATURAL VENTILATION
OR WITH MECHANICAL VENTILATION CAPABLE OF 60 cfm
EXHAUST DIRECTLY TO THE OUTSIDE
- HEATER SHALL BE CAPABLE OF MAINTAINING A MINIMUM
ROOM TEMPERATURE OF 68° F AT THE POINT 3 FEET ABOVE
THE FLOOR AND 2 FEET FROM EXTERIOR WALLS IN ALL HABITABLE
ROOMS AT THE DESIGN TEMPERATURE

PLANS APPROVED
as required by
CASE NO. 11-00000-0000
Planner: [Signature]
Community Planning Bureau
City of Los Angeles Planning Dept.
Date: 11/2/11



PROPOSED FIRST FLR PLN
1/4"=1'-0"

- EXISTING WALL TO REMAIN
- PROPOSED 2 x 4 WALL
- PROPOSED 2 x 6 WALL

By: [Signature]
Date: [Blank]